

Scheme No.	Scheme Name and Parish	PROWS Affected	Proposed Works	Rationale	Timescales
1	Bloomfield, Paulton	CL16/47	Surface a 110 metres section with compacted Type 1	Strategically important route from Winterfield Park to doctor's surgery, Bloomfield Nursing Home and Paulton Memorial Hospital.	April - August
2	Summer Lane, Combe Down	BC62/4	Tarmacking short section within flights of steps and a 110 metres section between two flights of steps.	Potholes and uneven surface pose a H&S risk to pedestrians on a well used semi-rural path. Works will complete a scheme start in 2019-20 Capital Program.	April - August
3	Cotswold Way, North Stoke	BA18/23 and 17	Reprofiling, removing potholes and resurfacing with Cotswold stone sections of two bridleways	Part of Cotswold Way and difficult to use in winter months. 75% grant funding.	April - July
4	Sydney Buildings, Bathwick	BC54/40	Refurbish risers and retarmac steps on 25 metres section fo steps	Poor state of steps poses a H&S risk to users on a well used urban footpath	September - December
5	Mountain's Lane, Farmborough	CL9/54	Remodelling and surfacing with Type 1 a 395 metre section of the byway	Path is impassable for pedestrians due to excess water collecting along byway	April - August
6	Mill Lane, Timsbury	CL21/45	Fabricating a manhole into a drain with trashguard	Water is currently bypassing an existing drain and eroding the surface making the byway difficult for equestrian and pedestrian users	April - June
7	Glass Path, Cameley	CL1/5	Excavate and surface 500 metre section of path with Type 1 to fines	The path runs through a Victorian glass dump; the glass is rising to the surface causing a significant risk to path users, particularly children and dogs.	April - November
8	Abbots Wood	BA27/15	Surface The Brambles footpath through Abbots Wood	Footpath is now on the edge of two large developments and is getting considerably increased useage. s106 funded.	April - July
9	St Clements Road	n/a	Create public footpath between St Clements Road and Dunster Road	Create pedestrian line to encourage non-motorised travel. s106 funded.	April - July
10	Polestar, Paulton	CL16/2	Stoning existing footpath	Footpath is now on the edge of a large developments and is getting considerably increased useage. s106 funded.	April - June

Location of 2020/21 PROW Capital Schemes



Bath & North East
Somerset Council

