



KEY (CONT.)

- Sign to be mounted on existing post
- Sign to be mounted on new post
- Sacrificial asphalt construction: 20mm surface course (AC6 dense surface), 85mm binder course (AC20 dense 100/150 binder course), 20mm layer of bedding sand above existing carriageway surface
- Skid resistance surfacing PSV 60+
- Provide and install Simmonsign black weebol
- 2.4m x 25m visibility splay in accordance with MIS for 20 mph speed limit
- Intervisibility between vehicles: existing side road junctions set 2.4m from edge of carriageway
- 3m x 15m visibility for the stop line

AECOM

PROJECT
B&NES LIVEABLE NEIGHBOURHOODS

CLIENT
B&NES
 Bath and North East Somerset

CONSULTANT
 AECOM
 Portwall Place, Portwall Lane,
 Bristol, BS1 6NA
 +44 (0)117 9017000 Tel
 +44 (0)117 9017099 Fax
 www.aecom.com

GENERAL NOTES

- Do not scale from this drawing. All dimensions and levels are in metres, unless otherwise stated.
- This drawing is for guidance only, the contractor shall be responsible for establishing the position and status of all statutory utility apparatus prior to commencing any works. The contractor shall coordinate and undertake all works in conjunction and agreement with the affected statutory utility companies as necessary. Contractor to refer to NRSWA information supplied.
- All new road markings are laid and signs erected in accordance with: Traffic Signs Manual, Chapter 5 (2018). The Traffic Signs Regulations and General Directions 2016 (TSRGD 2016)
- Topographical survey information has not been obtained for this scheme, OS references and mapping have been used.
- Crown copyright all rights reserved. 2023 OS Information provided by Bath and North East Somerset Council.

KEY

EXISTING FEATURES TO REMAIN

- ROAD MARKINGS
- TELEPHONE BOX
- SIGN POST AND PLATE
- L.C. LIGHTING COLUMN

PROPOSED FEATURES

- THERMOPLASTIC ROAD MARKINGS
- PROVIDE AND LAY RUBBER BOLT DOWN HB2 KERBS (REFER TO MANUFACTURER DETAILS FOR MORE INFORMATION)
- PROVIDE AND LAY RUBBER 135° QUADRANT (REFER TO MANUFACTURER DETAILS FOR MORE INFORMATION)
- SIGN TO BE MOUNTED ON EXISTING LIGHTING COLUMN

ISSUE/REVISION

NO	DATE	DESCRIPTION
C05	24/09/2024	STOP LINE AND SIGN UPDATE
C04	23/06/2024	ETRO DESIGN UPDATE
C03	13/06/2024	SIGN & VISIBILITY UPDATE
C02	26/03/2024	VISIBILITY & SIGNS AMENDED
I/R	DATE	DESCRIPTION

PROJECT NUMBER
 60668625 **FOR CONSTRUCTION**

SHEET TITLE
 LIVEABLE NEIGHBOURHOODS
 ETRO GENERAL ARRANGEMENT
 WINIFRED'S LANE/CAVENDISH ROAD

SHEET NUMBER
 60668625-ACM-04-DD-LL_ETRO-SHT-0101B